

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21733-00-00
Spot: NESESE Sec/Twnshp/Rge: 32-21S-34W
1250 feet from S Section Line, 1250 feet from E Section Line
Lease/Unit Name: HUTCHINSON Well Number: 1-2
County: FINNEY Total Vertical Depth: 2735 feet

Operator License No.: 5293
Op Name: HELMERICH & PAYNE, INC.
Address: 1579 E. 21ST ST.
TULSA, OK 74017

Conductor Pipe: Size _____ feet: \$88.89
Surface Casing: Size 8.625 feet: 308 WITH 185 SX CMT
Production: Size 5.5 feet: 2719 WITH 525 SX CMT
Liner: Size _____ feet: _____

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/11/2002 11:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX GEL SPACER TO 1100'. PUMP CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/11/2002 1:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2678'. PERFS AT 2527-68'. PUMPED DOWN 5 1/2" CASING 500# HULLS & 25 SX CMT, MUD SPACER TO 1100'. PUMPED 130 SX CMT TO SURFACE. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 25 SX CMT. PRESSURED UP TO 500# & SHUT IN.

RECEIVED
APR 21 2002
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Kevin D Strube

(TECHNICIAN)

INVOICED

APR 17 2002

DATE

4-23-02

INV. NO.

2002061687

[Signature]
FORM CP-2/3