

To: 1 20682
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-29 RECEIVED
KANSAS CORPORATION COMMISSION
WICHITA, KANSAS
JUL 01 1993
CONSERVATION DIVISION

API NUMBER 15-055-20,235.0000

App. C SW, SEC. 31, T 21 S, R 34 W/E

1324 feet from S section line

3867 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6594

Lease Name Norris Well # 1-31

Operator: Colorado Interstate Gas Exploration
Name &

County Finney

Address P.O. Box 749
Denver, CO 80201

Well Total Depth 2990 97.17 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 597

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Colorado Interstate Gas Exploration License Number 6594

Address P.O. Box 749, Denver, CO 80201

Company to plug at: Hour: 10 a.m. Day: 29 Month: 6 Year: 19 93

Plugging proposal received from Don DeHerrera

(company name) CIGE (phone) 303-573-4482

work: 4 1/2" at 2988' w/400 sx cement, PBTD 2950', Perfs at 2602-10'

1st plug set 4 1/2" CIBP at 2550' w/2 sx cement on top,

2nd plug perforate 4 1/2" casing at 1040' and pump 60 sx cement, 2 sx hulls, and 150 sx cement

down 4 1/2".

3rd plug pump 210 sx cement down annulus.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:20 p.m. Day: 29 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2550' with 2 sx cement on top,

2nd plug perforated at 1040' and pumped 60 sx cement, 2 sx hulls, and 150 sx Class H LC

65/35 6% gel cement down 4 1/2" casing.

Pressured up to 1250#, holding at 500#.

3rd plug pump 2 sx hulls in with first part of 210 sx cement down annulus. Pressured to 750#.

Shut in with 350# holding. Left valves on.

Remarks: Used Class H LC 65/35 6% gel cement by Halliburton. No casing recovery.
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 7-7-93

Signed Glenn R Barlow (TECHNICIAN)

INV. NO. 38041
6-29