

To: 1120706 4-30
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,836.0000 262
R

SE SW SE, SEC. 34, T. 21 S, R. 12 W/E
330 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3182

Lease Name Robert Siefkes Well / A 1

Operator: NPF Energy Corporation

County Stafford

Name: _____

Well Total Depth 3640 118.30 feet

Address P.O. Box 3827

Conductor Pipe: Size _____ feet

Tustin, CA 92681-3827

Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 3 p.m. Day: 30 Month: 4 Year: 19 92

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 638-659'

1st plug at 660' with 50 sx cement,

2nd plug at 390' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:15 p.m. Day: 30 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 660' with 50 sx cement,

2nd plug at 390' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO.

(if additional description is necessary, use BACK of this form)

observe this plugging.

DATE 5-15-92

NV. NO. 35253

Signed Steve Pfeifer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1992
CONSERVATION DIVISION
WICHITA, Kansas

EFFECTIVE DATE: 4-25-92

FORM MUST BE TYPED

DISTRICT # 1
SEAT X No

State of Kansas 15
NOTICE OF INTENTION TO DRILL 185-22,836.0000 ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date April 25, 1992 Spot SW SE 1/4 Sec 34 Twp 21 S, Rg 12 East X West

OPERATOR: License # 03182
Name: NPF ENERGY CORPORATION
Address: P.O. BOX #100
City/State/Zip: TUSTIN, CALIF. (C=C*! F*@&
Contact Person: Mr. Pat H. Cochran
Phone: 714.543-8846

330 feet from South / 1650 feet from East / XX REGULAR IRREGULAR
(NOTE: Locate well on the Section Plat on Reverse Side)
County: Stafford
Lease Name: Robert Siefkes, A # 1
Field Name: Max

CONTRACTOR: License # 6039
Name: L. D. Drilling, Inc.

Is this a Prorated/Spaced Field? yes XX no
Target Formation(s): Arbuckle
Nearest Lease or unit boundary: 330
Ground Surface Elevation: 182 feet MSL
Water well within one-quarter mile: X yes no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 100
Depth to bottom of usable water: 200
Surface Pipe by Alternates: X 1 2
Length of Surface Pipe Planned to be set: 260
Length of Conductor pipe required: none
Projected Total Depth: 3650
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
X well farm pond X other
D&R Permit #: _____
Will Cores Be Taken?: yes X no
If yes, proposed zone: _____

Well Drilled For: Well Class: Type Equipment:
XX Oil ... Enh Rec X Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... DWWD ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other
... Other
If DWWD: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth: _____
Bottom Hole Location: _____

Exp. 10/20/92 AFFIDAVIT 220' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Greg Davidson
SPUD DATE 4-25-92 INIT. OG
LENGTH SURFACE PLANNED 300'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 360' CONDUCTOR
ANHYDRITE T- 638 B- 659 ELEVATION
TD 3640 FORMATION Consistency
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
1 Anhydrite Base @ 1660 Ft. W/ 50SX
 1/2 Base Anhyd. @ Ft. W/ SX
 1/2, 1/2 Plug @ Ft. W/ SX
2 Bottom Surface @ 390 Ft. W/ 50SX
3 40' Plug @ 40 Ft. W/ 10SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond)
TECHNICIAN SP DATE 4-30-92 Hauling
TYPE OF CEMENT DATE 4-30-92
STARTING TIME (AM/PM) DATE
COMPLETION TIME (AM/PM) DATE
CEMENT COMP. DATE (AM/PM) DATE

RECEIVED
MAY 6 1992
WARRANTY DIVISION
COMPLETION TIME
CEMENT COMP. DATE