

To: 1 040720 11-20
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,125-0000 115P
SW SE SW, SEC. 34, T 21 S, R 12 W/E
330 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3493
Operator: Reginald Fisher Oil Company
Name & Address: 110 N. Exchange
St. John, KS 67576

Lease Name Wittrock Well # 1
County Stafford
Well Total Depth 3624 117.78 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 681

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 20 Month: 11 Year: 1992

Plugging proposal received from David Bradey
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Work: 5 1/2" at 3621' w/200 sx cement, PBTB 3590', Perfs at 3466-70, 3406-08, 3319-22, 3624-30'
1st plug sand back to 3270' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 125 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 p.m. Day: 20 Month: 11 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3270' and dumped 5 sx cement on top of sand bridge through bailer,
2nd plug pumped down the 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 125 sx cement.

Maximum pressure 600 psi and shut in 400 psi.

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1992

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 07 1992
INV. NO. 36980

(did not) observe this plugging.

Signed *Stephan J. Fisher*
(TECHNICIAN)