

051384

12-27

291R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,069.0000

C N/2 NW NE SEC. 34, T 21 S, R 12 W/E

4950 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Siefkes A Well # 6

Operator: Phillips Petroleum Company
Name & Address: Route 3, Box 20-A
Great Bend, KS 67530

County Stafford 125.22

Well Total Depth 3853 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 27 Month: 12 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

logs: 5 1/2" at 3655' w/170 sx cement, PBD 3622', Perfs at 3304-3504' (7 sets)

1st plug sand back to 3280' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:15 p.m. Day: 27 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3280' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 50 psi.

1-4-91

RECEIVED STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2320' of 5 1/2" casing. 12/21/91
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

observe this plugging.

Page # B842638

Signed Richard W. Lacey (TECHNICIAN)

DATE 1-28-91

Charge # 80-7129

INV. NO. 30557

12-27