

1120558

4-22

422

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

AP# NUMBER 19-185-22,563.0000

NE SE NW, SEC. 34, T. 21 S, R. 12 W/E

3630 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9354

Lease Name Williamson Well # 1

Operator: Central Energy Corporation

County Stafford 118.36

Name & Address P.O. Box 47590

Well Total Depth 3642 feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 22 Month: 4 Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 3637', Open hole at 3637-42'

1st plug sand back to 3585' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 22 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3585' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 125 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2400' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

(If possible, observe this plugging.)

Signed Duane Rankin (TECHNICIAN)

INVOICED

DATE 5-9-91

INV. NO. 31779