

1 010176

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-20,809.0000
NW NW NW, SEC. 34, T 21 S, R 12 W/R

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588

Operator: Woodman-Iannitti Oil Company
Name & Address Box 308
Great Bend, KS 67530

4950 feet from S section line

4950 feet from E section line

Lease Name Williamson Well # 3

County Stafford 121.55

Well Total Depth 3740 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 293

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 12:50 p.m. Day: 13 Month: 10 Year: 19 86

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3640' PBTD 3540' Perfs 3400-04'

1st plug sand back to 3350' and dump 5 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls, 40 sx gel, and 100 sx lite cement

Plugging Proposal Received by Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:20 p.m. Day: 13 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3350' and dumped 5 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls, 40 sx gel, and 100 sx Econolite cement

OFFICE OF THE COMMISSIONER OF CONSERVATION
WICHITA, KANSAS

10-15-86

Maximum pressure 600 psi and shut in 350 psi. OCT 15 1986

Remarks: Recovered 2700' of 5 1/2". Used Econolite by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED (void) observe this plugging.

DATE 10-15-86

Signed [Signature]
(TECHNICIAN)

INV. NO. 15175