

To: 1090074  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200-COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-24  
API NUMBER 15-185-22,769.0000 421 R

NE SE SE, SEC. 12, T. 21 S, R 12 W/R  
990 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7916

Lease Name Osborne Well # 2

Operator: Eldon J. Schierling

County Stafford 117.00

Name & Address 333 E. English, Suite 240

Well Total Depth 3600 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Company License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour 3:30 p.m. Day: 24 Month: 4 Year: 19 91

Plugging proposal received from Leonard Williamson

(company name) Duke Drilling Company (phone) 316-267-1331

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at Arbuckle with 40 sx cement, 2nd plug at 613' with 50 sx cement,

3rd plug at 350' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 7 p.m. Day: 24 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 3475' with 40 sx cement,

2nd plug at 620' with 50 sx cement,

3rd plug at 350' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

Water well filled with cement.

REMARKS: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED ~~XXXXX~~ due to observe this plugging:

DATE 5-13-91

INV. NO. 31801

Signed [Signature]  
(TECHNICIAN)

EFFECTIVE DATE: 4-24-91

FORM MUST BE TYPED  
FORM C-1 4/90

State of Kansas

NOTICE OF INTENTION TO DRILL

FAX

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date April 19, 1991  
month day year

NE.. SE., SE... Sec 12. Twp 21. S, Rg 12.  East  West  
990 feet from South line of Section  
330 feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

OPERATOR: License # 7916  
Name: ELDON J. SCHIERLING  
Address: 333 East English - Suite 240  
City/State/Zip: Wichita, Kansas 67202  
Contact Person: Eldon J. Schierling  
Phone: 316/267-0042

County: Stafford  
Lease Name: Osborne Well #: 2  
Field Name: Unknown  
Is this a Prorated Field? ... yes  no  
Target Formation(s): Lansing, Arbuckle  
Nearest lease or unit boundary: 330'  
Ground Surface Elevation: 450' Unknown feet MSL  
Domestic well within 330 feet: ... yes  no  
Municipal well within one mile: ... yes  no  
Depth to bottom of fresh water: 100'  
Depth to bottom of usable water: 220'  
Surface Pipe by Alternate:  1  2  
Length of Surface Pipe Planned to be set: 240'  
Length of Conductor pipe required: N/A  
Projected Total Depth: 3525  
Formation at Total Depth: Arbuckle  
Water Source for Drilling Operations:  
... well ... farm pond  other

CONTRACTOR: License #: 5929  
Name: DUKE DRILLING CO., INC.

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Inj  Infield  Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWMO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes

If OWMO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? ... yes  no  
If yes, total depth location: \_\_\_\_\_

DWR Permit #: \_\_\_\_\_  
Will Cores Be Taken?: ... yes  no  
If yes, proposed zone: 250' Alt. I Req.

Exp. 10/20/91

AFFIDAVIT

*\*250' of surface pipe required*

Pusher Remond Williams  
SPUD DATE 4-19-91 INIT.

LENGTH SURFACE PLANNED \_\_\_\_\_  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 3/8 @ 309 CONDUCTOR  
ANHYDRITE T- B ELEVATION  
TD 5600 FORMATION 3500 - Osborne

RAN PIPE @ SX DV TOOL SX ALT II DONE Y N  
Arbuckle Plug @ 3475 Ft. W/ 40 SX  
Hug./Council @ 620 Ft. W/ SX  
Anhydrite Base @ 613 Ft. W/ 50 SX  
1/2 Base Anyh. @ 350 Ft. W/ 50 SX  
1/2, 1/2 Plug @ Ft. W/ SX  
Bottom Surface @ Ft. W/ SX  
40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX  
WATER WELL filled SX (Irr. Well Pond Hauling  
TECHNICIAN SM DATE 4-22-91

TYPE OF CEMENT 60/40 690  
STARTING TIME 3:30 (AM/PM) DATE  
COMPLETION TIME 7 (AM/PM) DATE 4-24-91  
CEMENT COMPANY Allied