

1 090141

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,128 .0000

SW SW SE, SEC. 3, T 21 S, R 24 W/E

330 feet from ~~N~~/S section line

2310 feet from ~~W~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6999 & 7030

Lease Name Donny Betz Well # 1

Operator: John Roy Evans & Antares Oil Corp.
Name & Address Suite 200, 1801 California St.
Denver, CO 80202

County Hodgeman

Well Total Depth 4460. 144.95 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co., Inc. License Number 5929

Address P. O. Box 823, Great Bend, KS 67530

Company to plug at: Hour: 3:00 am Day: 6 Month: March Year: 19 84

Plugging proposal received from Bill Draney

(company name) Duke Drilling (phone) 316-793-8366

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1500' with 50 sx cement

2nd plug at 510' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by R. Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:25 am Day: 6 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement, 2nd plug at 510' with 50
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rathole with 15 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 3-13-84
INV. NO. 0722

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1984

Signed R. Barluttan
(TECHNICIAN) ✓

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84