

1 120218

2-1

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 60' S
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,797.0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588

Operator: Woodman-Iannitti Oil Company
Name &
Address Box 308
Great Bend, KS 67530

NW SW NW SEC. 28, T 21 S, R 12 W
3570 feet from S section line
4950 feet from E section line

Lease Name Grow Well # 3

County Stafford 120.77

Well Total Depth 3716 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 1 Month: 2 Year: 19 89

Plugging proposal received from James Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3713' PBD 3660' Perfs at 3597-99'

1st plug sand back to 3540' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 120 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
2-3-1989
5 1989

Plugging Proposal Received by Paul Luthi

(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 1 Month: 2 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3540' and dumped 5 sx cement
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug, and pumped 120 sx cement.

Pumping pressure 0-650 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2936' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 2-8-89

Signed Paul Luthi
(TECHNICIAN)

INV. NO. 23914
2-1