

1 030359

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,151.0000
150' S of
NE NE NE , SEC. 28 , T 21 S, R 12 W/E

4800 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039
Operator: L.D. Drilling, Inc./L.D. Davis
Name & Address: R. R. 1, Box 183B
Great Bend, KS 67530

Lease Name Ziegenbusch Farms Well # 1
County Stafford 117.72
Well Total Depth 3622 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 301 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x

Other well as hereinafter indicated _____

Plugging Contractor L. D. Drilling, Inc. License Number 6039

Address R. R. 1, Box 183B, Great Bend, KS 67530

Company to plug at: Hour: 8:30 am Day: 8 Month: January Year: 19 85

Plugging proposal received from Don Pope

(company name) L. D. Drilling (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 660' with 50 sx cement

2nd plug at 330' with 40 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

Plug water well with 5 sx cement (top to bottom)

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:15 am Day: 8 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 660' with 50 sx cement, 2nd plug at 330' with 40 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, and plugged water

well top to bottom with 5 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED

(if not) observe this plugging.

DATE 1-18-85

Signed Steve Durrant (TECHNICIAN)

INV. NO. 6600