

1 040889

15.185.12249.0001

9-12

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-22,348

SW SE NW, SEC. 28, T. 21 S, R. 12 W/E

2970 feet from S section line

3630 feet from E section line

Lease Name Grow Well # 4

County Stafford

Well Total Depth 3895 12658 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 230

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588

Operator: Woodman-Iannitti Oil Co.

Name & Address P.O. Box 308

Great Bend, KS 67530

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 12 Month: 9 Year: 19 94

Plugging proposal received from Manny Boatwright

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Work: 5 1/2" at 3764' w/125 sx cement, Open hole 3764-3895', R-4 HOWCO packer left in hole at 3755'

Sanded back on top of packer.

1st plug sand back to 3705' and dump 5 sx cement on top of sand bridge through bailer.

2nd plug pump down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 12 Month: 9 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 3705' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pump 125 sx cement.

Maximum pressure 800 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1800' of 5 1/2" casing.

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE SEP 27 1994 observe this plugging.

DATE 41281

REV. NO. 41281

Signed Stephen J. Pfeifer (TECHNICIAN)