

1052397

TO: STATE CORPORATION COMMISSION API NUMBER 15-185-20,555-0001
71'N 71'E NW SW SW SEC. 24, T 21 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 1061 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 401 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME WILSON WELL # 1 OWWO

TECHNICIAN'S PLUGGING REPORT 6/6 COUNTY STAFFORD 119.18

OPERATOR LICENSE # 6039 WELL TOTAL DEPTH 3667 FEET

OPERATOR: L.D. DRILLING, INC. PRODUCTION CSG: SIZE 5 1/2" @ 3665' WITH 175 SX

NAME AND RR 1, BOX 183 B SURFACE CASING: SIZE 8 5/8" @ 322' WITH 275 SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DS&W WELL SERVICING LICENSE NUMBER 6901

ADDRESS PO BOX 231 CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 12:00 PM DAY: 06 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM BRIAN FRENZL

(COMPANY NAME) DS&W (PHONE) 316-587-3816 RECEIVED STATE CORPORATION COMMISSION

JUN 19 2000

WERE: PERFS AT 3517-3531, 3321-3326

1ST PLUG SAND TO 3270' AND 5 SX CEMENT. 2ND PLUG AT 700' WITH 50 SX CEMENT CONSERVATION DIVISION
Wichita, Kansas

3RD PLUG AT 360' WITH 50 SX CEMENT, 4TH PLUG AT 40' WITH 20 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 1:15 PM DAY: 06 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG SAND BACK TO 3270' AND 5 SX CEMENT. 2ND PLUG AT 700' WITH 50 SX CEMENT.

3RD PLUG AT 360' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 20 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2700' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID NOT) OBSERVE THIS PLUGGING DATE 6/21/00 SIGNED

Richard M. Lacey
(TECHNICIAN)

INV. NO. 61887

FORM CP-2/3

