

12-30

To: 1 051114
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,564.0000
SE SE SE, SEC. 6, T 21 S, R 12 W&E
330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT RECEIVED
STATE CORPORATION COMMISSION

Operator License # 6039
Operator: L.D. Drilling, Inc. JAN - 4 1989
Name & Address: RR 1, Box 183 B
Great Bend, KS 67530
CONSERVATION DIVISION
Wichita, Kansas

Lease Name August Well # 2
County Stafford 115, 38
Well Total Depth 3550 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 6 a.m. Day: 30 Month: 12 Year: 19 88

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 660-682'

1st plug at 3400' with 50 sx cement, 2nd plug at 690' with 50 sx cement,

3rd plug at 300' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:30 a.m. Day: 30 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 3400' with 50 sx cement,

2nd plug at 690' with 50 sx cement,

3rd plug at 300' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

Water well plugged with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
(did not) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 1-9-89

INV. NO. 23561

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date December 20 1988

API Number 15-185-22,564.0000

OPERATOR: License # 6039
Name D. Drilling, Inc.
Address R.R. 1, Box 183, R.
City/State/Zip Great Bend, Kansas 67530
Contact Person L. D. Davis
Phone (316) 793-3051

SE SE SE Sec. 6 Twp. 21 S, Rg. 12
330 Ft. from South Line of Section
330 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County STAFFORD

CONTRACTOR: License # 6039
Name L. D. Drilling, Inc.
City/State Great Bend, Ks. 67530

Lease Name AUGUST Well # 2
Ground surface elevation APPROX. 1853 feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water 100'
Depth to bottom of usable water 280' 230'

Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 250'

Conductor pipe required
Projected Total Depth 3570 feet

Formation Arbuckle

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 12-15-88 Signature of Operator or Agent Bessie Dewert Title Agent

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 250' feet per Alt. 1 X
This Authorization Expires 6-16-89 Approved By LKM 12-16-88

EFFECTIVE DATE 12-21-88

RECEIVED 12-21-88
STATE CORPORATION COMMISSION
JAN 4 1989

SET 278' OF 8 5/8 ON 12-21-88

SE SE SE Sec. 6 Twp. 21 S, Rg. 12 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal is to be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 50' into arbuckle.. feet depth with 40... sxs of...
2nd plug @ Any... feet depth with 50... sxs of...
3rd plug @ 30' out of surface.. feet depth with 50... sxs of...
4th plug @ 40' - 0 Solid bridge feet depth with 10... sxs of...
5th plug @ ... feet depth with ... sxs of...
(2) Rathole with 15... sxs
(b) Mousehole with ... sxs

PUSHER Greg Davidson
TD 3550 FORMATION Arb
SURFACE PIPE 8 5/8 @ 218
ANHYDRITE 660-682 ELEVATION
STARTING TIME & DATE 6:00 AM 12-30-88
COMPLETION TIME & DATE 9:30 AM 12-30-88
1st PLUG @ 278 FT. W/ 50 SX
2nd PLUG @ 690 FT. W/ 50 SX
3rd PLUG @ 700 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ Sillw 10 SX
CEMENT COMPANY Allied
TECHNICIAN Lacey
60/40 60b
Plugged