

1 050626

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,278.0000
70' N & 170' W
SE SE SE , SEC. 6 , T 21 S, R 12 (W)E
400 feet from S section line
500 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name August Well # 1

Operator: L. D. Drilling, Inc.
Name & Address R. R. 1, Box 183 B
Great Bend, KS 67530

County Stafford 115.38 ✓

Well Total Depth 3550 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor L. D. Drilling, Inc. License Number 6039

Address R. R. 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 6:00 am Day: 12 Month: September Year: 1985

Plugging proposal received from Don Pope

(company name) L. D. Drilling (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug in the Arbuckle if 50' or more with 40 sx cement

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug 30' out of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:00 am Day: 12 Month: September Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 690' with 50 sx cement, 2nd plug at 300' with 40 sx
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 15 sx cement

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 24 1985

INV. NO. 10207

Signed Richard W. Lacey
(TECHNICIAN)