

1091000

TO: STATE CORPORATION COMMISSION

7-17

API NUMBER 15-083-21,459.0000
APP. C SW SEC. 15, T 21 S, R 24 W

CONSERVATION DIVISION - PLUGGING SECTION 1300 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1330 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MCGAUGHEY WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY HODGEMAN 150.15

OPERATOR LICENSE # 5046

WELL TOTAL DEPTH 4620 FEET

OPERATOR: RAYMOND OIL COMPANY PRODUCTION CSG: SIZE " FEET

NAME AND PO BOX 48788 SURFACE CASING: SIZE 8 5/8" @ 252' WITH SX

ADDRESS WICHITA, KS 67201-8788

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DUKE DRILLING LICENSE NUMBER 5929

ADDRESS 100 S MAIN, SUITE 410, WICHITA, KS 67202-3737

COMPANY TO PLUG AT: HOUR: 11:45 PM DAY: 16 MONTH: 07 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE

(COMPANY NAME) DUKE DRILLING (PHONE) 316-267-1331

WERE:

1ST PLUG AT 1250' WITH 50 SX CEMENT. 2ND PLUG AT 700' WITH 80 SX CEMENT.

3RD PLUG AT 280' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:45 AM DAY: 17 MONTH: 07 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1250' WITH 50 SX CEMENT.

2ND PLUG AT 700' WITH 80 SX CEMENT.

3RD PLUG AT 280' WITH 50 SX CEMENT.

4TH PLUG TO 40' WITH 10 SX CEMENT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

STATE CORPORATION COMMISSION

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

DATE JUL 22 1999

JUL 21 1999 SIGNED

(TECHNICIAN)

FORM CP-2/3

INV. NO. 60060

CONSERVATION DIVISION
Wichita Kansas

7-21-99

(2)