

To: 1 090175  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

3-10

API NUMBER 15- 083-21,375.0000

94  
R

TECHNICIAN'S PLUGGING REPORT

Operator License # 30342  
Operator: Sheets Oil Company  
Name & Address: 1333 W. 120th, Ste. 310  
Westminster, CO 80234

W/2 NE SE; SEC. 5, T. 21 S, R. 24 W/E  
1980 feet from S section line  
990 feet from E section line  
Lease Name Kline Well # 1-A  
County Hodgeman  
145.43  
Well Total Depth 4475 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling Company License Number 5418

Address P.O. Box 1389, Great Bend, KS 67530-1389

Company to plug at: Hour: 9 p.m. Day: 10 Month: 3 Year: 19 92

Plugging proposal received from Vince Schrapel

(company name) Allen Drilling Company (phone) 316-793-5681

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1506-20'  
1st plug at 1530' with 50 sx cement, 2nd plug at 600' with 80 sx cement,  
3rd plug at 280' with 50 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None \_\_\_\_\_ X

Operations Completed: Hour: 11:15 p.m. Day: 10 Month: 3 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement,  
2nd plug at 600' with 80 sx cement,  
3rd plug at 280' with 50 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

RECEIVED  
3-19-1992  
MAR 19 1992

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

**INVOICED**

(did not) observe this plugging.

DATE 4-7-92  
INV. NO. 34895

Signed [Signature]  
(TECHNICIAN)

FOR KCC USE:

EFFECTIVE DATE: 3-4-92

DISTRICT: 1

SEAT: X Yes No

02/28/92 16:00 P. 1 TOTAL P. 1

FORM G-1 7/91 FROM

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

State of Kansas 15-083-21,375.0000  
NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date March 2, 1992  
month day year

Spot East  
C W/2-NE/4 SE/4 Sec 5... Twp 21 S. s, Rg 24... X West

OPERATOR: License # 30342  
Name: SHEETS OIL CO.  
Address: 1333 W. 120th, Ste #310  
City/State/Zip: Westminster, Co. 80234  
Contact Person: Rich O'Donnell  
Phone: 303/426-9722 (303) 451-0175

1980' feet from South X 26th line of Section  
990' feet from East X 26th line of Section  
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Hodgeman

CONTRACTOR: License # 5418  
Name: ALLEN DRILLING COMPANY

Lease Name: KLINE Well #: 1-A  
Field Name: UNLAMED

Is this a Propped/Spaced Field? yes X no  
Target Formation(s): Mississippian

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Enh Rec X Infield X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... GUVG ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes ... Other  
... Other

Nearest lease or unit boundary: 990'  
Ground Surface Elevation: 2274' feet MSL

Water well within one-quarter mile: yes X no  
Public water supply well within one mile: yes X no

If GUVG: old well information as follows:  
Operator: N/A  
Well Name: N/A  
Comp. Date: N/A Old Total Depth

Depth to bottom of fresh water: 100'  
Depth to bottom of usable water: 675'

Surface Pipe by Alternates: 1 X 2  
Length of Surface Pipe Planned to be set: 250'

Length of Conductor pipe required: N/A  
Projected Total Depth: 4550'

Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, true vertical depth:  
Bottom Hole Location:

X well farm pond other

DNR Permit #: N/A  
Will Cores Be Taken?: yes X no  
If yes, proposed zone:

Exp. 8/29/92 200' Alt. II Req.

APPENDIX

\* Alternate 2 completion

Pusher Vince  
SPUD DATE 3-2-92 INIT.  
LENGTH SURFACE PLANNED 250'  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 7/8 @ 206 CONDUCTOR  
ANHYDRITE T- 1506 B- 1520 ELEVATION  
TD 4475' FORMATION M.S.S.  
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N  
Arbuckle Plug @        Ft. W/ SX  
Hug./Council @        Ft. W/ SX  
1 Anhydrite Base @ 1530 Ft. W/ 50 SX  
2 1/2 Base Anyh. @ 600 Ft. W/ 80 SX  
1/2, 1/2 Plug @        Ft. W/ SX  
3 Bottom Surface @ 280 Ft. W/ 50 SX  
4 40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 1 1/2 SX MOUSE HOLE W/ SX  
WATER WELL SX (Irr. Well        Pond       )  
Hauling         
TECHNICIAN SM DATE 3-6-92  
TYPE OF CEMENT 60/40 60  
STARTING TIME 9:00 (AM/PM) DATE 3-10-92  
COMPLETION TIME 11:15 (AM/PM) DATE 3-10-92  
CEMENT COMPANY Halliburton DG