

4-061027

12-19

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-21,536-00-00
C NE SW /4 SEC. 33, 16 S, 12 W
4620 feet from S section line
4620 feet from E section line

Operator license# 4424

Lease Schneweis Well # 1

Operator: Smokey Valley Resources

County: Barton

Address: Rt. 3 - Box 63
Lyons, Kansas 67554-9404

Well total depth 3343 108.64 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 284 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Quality Well Service, Inc. License# 31925

Address: 249 E. Beth Dr. Sterling, Kansas 67579

Company to plug at: Hour: 9:00 A.M. Day: 19 Month: December Year: 1996

Plugging proposal received from: Richard McIntyre

Company: Quality Well Service, Inc. Phone: 316-278-2476

Were: Order 225 sxs 60/40 posm-x - 10% gel and hulls.
Plug while pulling casing.

RECEIVED
DEC 24 1996
AFCO

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 11:30 A.M., Day: 19, Month: December, Year: 1996

12-24-1996

Actual plugging report: 8 5/8" to 284' w/165 sxs. 5 1/2" to 3400' w/125 sxs. Sanded to 3290' and spotted 5 sxs cement with dump bailer. Shot casing loose at 1926' and pulled to 1450'. Mixed and pumped 100 sxs cement with 300# hulls. Pulled casing to 800' and pumped 35 sxs cement with 150# hulls. Pulled casing to 400' and pumped 35 sxs cement with 150# hulls. Pulled casing to 150' and circulated cement with 20 sxs. Pulled casing with cement in cellar.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 1862 GL

I did not observe the plugging.

INVOICED
DATE JAN 08 1997
INV. NO. 47246

DP (agent)
Form CP-2/3

12-19 MAR 14 1997