

4-061029

12-20

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-22,505-0000
100'E.of
S2 N2 SW /4 SEC. 33, 16 S, 12 W
4290 feet from S section line
3860 feet from E section line

Operator license# 4424

Lease Schneweis Well # 2

Operator: Smokey Valley Resources

County: Barton

Address: Rt. 3 - Box 63
Lyons, Kansas 67554-9404

Well total depth 3347 108.77 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 282 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Quality Well Service, Inc. License# 31925

Address: 249 E. Beth Dr. Sterling, Kansas 67579

Company to plug at: Hour: 9:00 A.M. Day: 20 Month: December Year: 1996

Plugging proposal received from: Richard McIntyre

Company: Quality Well Service, Inc. Phone: 316-278-2476

Were: Order 225 sxs 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.

RECEIVED
NOV 13 1996
PLUGGING DIVISION
STATE CORPORATION COMMISSION
WICHITA, KANSAS

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[X], None[] 12-24-1996


Completed: Hour: 10:30 A.M., Day: 20, Month: December, Year: 1996

Actual plugging report: 8 5/8" to 282' w/185 sxs. 5 1/2" to 3344' w/125 sxs. O.H. 3344' - 3347'. Sanded to 3290' and spotted 5 sxs cement with dump bailer. Shot casing loose at 2006' and pulled to 1450'. Mixed and pumped 100 sxs cement with 300# hulls. Pulled casing to 800' and pumped 35 sxs with 150# hulls. Pulled casing to 400' and pumped 30 sxs cement with 150# hulls. Pulled casing to 150' and circulated cement with 20 sxs. Pulled casing with cement in cellar.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1880 GL

INVOICED
If bid [] / mile not [X] observe the plugging.


(agent)

DATE JAN 03 1997

INV. NO. 47247

12-20 MAR 14 1997