

State of Kansas



15.185.30343.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

DEC 5 1966

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

CONSERVATION DIVISION
Wichita, Kansas

12-5-1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. George Sowles of Abercrombie Drilling, Inc has this date requested permission to plug the following described well:

Mr. Sowles guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Inc.

Complete Address: 801 Union Center Bldg., Wichita, Kansas

Lease Name: Walker Well No. # 1

Location: NE NW SW Sec. 33 Twp. 21 Rge. 12 (E)(W) W

County Stafford Total Depth 3363' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sowles was instructed to plug the well as follows:

311' of 8 5/8" surface pipe, cement circulated. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of the cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent