



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

MAY 5 - 1972
05-05-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John H. Knightly of D. R. Lauck Oil Co., Inc. has this date requested permission to plug the following described well:

Mr. D. R. Lauck Oil Co., Inc. guarantees payment of the plugging fee.

Operator's full Name: D. R. Lauck Oil Company, Inc.

Complete Address: 301 S. Broadway, Wichita, Kansas 67202

Lease Name: Oeser Well No. # 5

Location: C SW NW SE Sec. 25 Twp. 16 Rge. 12 (E)(W) W

County: Barton Total Depth 3264 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. R. E. Smith was instructed to plug the well as follows:

7" csg. 376'. Cable tool hole. 7" csg. not cemented.

Set plug @ 2487' & dumped 5 sax cement with dump bailer. Pulled pipe,

525' of 5½" casing, Set plug in bottom of 7" csg. Shot hole in 7" csg.

@ 340'. Circulated same with 25 sax mud & 30 sax cement with Globe

Cementing Company's pump truck, cementing from 340' to base of cellar.

Very truly yours,

Don Lewis
Conservation Division Agent