



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 11 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Brody of Thunderbird has this date requested permission to plug the following described well:

Mr. Brody guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling & Petro Resources

Complete Address: Box 18407, Wichita, Kansas

Lease Name: McNair Well No. 1

Location: NW SE Sec. 9 Twp. 21 Rge. 24 (E) (W)

County: Hodgeman Total Depth 4450' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Brody was instructed to plug the well as follows:


8 5/8" to 250' circulated w/ cement. Mud 4450' to 850'

Spot 80 sacks cement 850' to 550' Mud 550' to 200'

Spot 30 sacks cement 200' to 100' Mud 100' to 40'

Plug, Halls & 15 sacks cement 40' to 0'

Very truly yours,

  
Conservation Division Agent