



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 8 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Spah of Texaco Inc. has this

date requested permission to plug the following described well:

Mr. Spah guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 217 North Harvey, Oklahoma City, Oklahoma

Lease Name: Nicholas Geebel Well No. 1

Location: C SW NW Sec. 21 Twp. 21 Rge. 24 ~~(E)~~ (W)

County: Hodgeman Total Depth 4625' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Spah was instructed to plug the well as follows:

8 5/8" to 293' circulated w/ cement. Mud 4625' to 720'

Spot 70 sacks cement 720' to 480' Mud 480' to 270'

Spot 20 sacks cement 270' to 190' Mud 190' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent