



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 17 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Gowdy of Rains & Williamson has this date requested permission to plug the following described well:

Mr. Gowdy guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Co.

Complete Address: 220 W. Douglas, Wichita, Kansas

Lease Name: ~~XXXX~~ Adams Well No. 1

Location: NE SW SW Sec. 21 Twp. 21 Rge. 24 (E) (W)

County: Hodgeman Total Depth 4570' Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Gowdy was instructed to plug the well as follows:

8 5/8" to 307' circulated w/ cement. Mud 4570' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 300'

Spot 30 sacks cement 300' to 200' Mud 200' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent