

State of Kansas



15.185.20013.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 7 1967
CONSERVATION DIVISION
Wichita, Kansas
3-7-1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill, filed
February 23, 1967.

Dear Sir:

Mr. Clarence Michaels of Sage Drilling Co., Inc. has this
date requested permission to plug the following described well:

Mr. Michaels guarantees payment of the plugging fee.

Operator's full Name: Jay-Bee Oil Company, Inc.

Complete Address: 515 Union Center Bldg., Wichita, Kansas

Lease Name: Grow Well No. # 1

Location: NE NW NW Sec. 28 Twp. 21 Rge. 12 (E)(W) W

County Stafford Total Depth 3678' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Michaels was instructed to plug the well as follows:

288' of 8 5/8" surface pipe, cement circulated. Fill hole with
drilling mud to 280', 1st cementing plug, bridge with 1/2 sack of hulls,
and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd
cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent