

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 18 1966
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Sam Stevens of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Stevens guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 300 W. Douglas, Wichita, Kansas

Lease Name: Sittner "D" Well No. # 4

Location: SW NW SE Sec. 28 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3280' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Stevens was instructed to plug the well as follows:

249' of 8 5/8" surface pipe, cement circulated. Fill hole with drilling mud to 240', 1st cementing plug, bridge with 1/4 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,
Archie Elving