



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 9 1964

CONSERVATION DIVISION
Wichita, Kansas

3-9-1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of Graves Drilling C., Inc has this
date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: John C. Graves & Meltzer Oil Co.

Complete Address: 412 Union Center, Wichita, Kansas

Lease Name: Walker Well No. # 3

Location: NE NW SE Sec. 32 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3628 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

271' of 8 5/8" surface pipe, cemented with 310 sacks.

Fill hole with drilling mud to 265', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2' sacks.

Very truly yours,

Archie Elving
Conservation Division Agent