



15.185.20555.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

DEC 26 1974

CONSERVATION DIVISION
Wichita, Kansas

12-26-1974

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Copeland of Lauch Drlg Co has this

date requested permission to plug the following described well:

Mr. Copeland guarantees payment of the plugging fee.

Operator's full Name: Kansas Petroleum Inc

Complete Address: 500 Insurance Bldg Wichita, KS

Lease Name: Wilson Well No. 2

Location: 100' NE/NW/SW/SW Sec. 24 Twp. 21s Rge. 12 (E) (W) W

County: Stafford Total Depth 3676 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Copeland was instructed to plug the well as follows:

322 ft 8 5/8 surface cemented with 300 sacks. Pump plug,

40 sacks cement to 500 ft. 2nd plug at 300 ft, 35 sacks

cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks

cement to surface. 2 sacks cement in rat hole.

Pumped by Halliburton Cementing Great Bend, KS

Very truly yours,

Conservation Division Agent