



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 19 1964  
10-19-1964  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

10-9-64

Dear Sir:

Mr. Self of Self Casing Pulling Company has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company Incorporated

Complete Address: 410 4th National Bank Building, Wichita, KANSAS

Lease Name: Stevenson A Well No. #1

Location: SW-NW-NW Sec. 261 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3638 Oil Well W

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Self was instructed to plug the well as follows:

250 feet of 8 5/8 inch surface pipe circulated with cement. 3630 feet of 5 1/2 inch long string, perforated at 3375; sand to 3350 feet cemented with 3 sacks, mud to 250 feet, 10 feet rock bridge, cemented with 25 sacks; mud to 40 feet; 10 feet rock bridge cemented with 10 sacks to base of cellar.

Very truly yours,

Conservation Division Agent