

State of Kansas



15.185 20009.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

FEB 21 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed February 9, 1967

Dear Sir:

Mr. George Foster of Abercrombie Drilling, Inc has this  
date requested permission to plug the following described well:

Mr. Foster guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Inc.

Complete Address: 801 Union Center Bldg., Wichita, Kansas

Lease Name: Stevenson Well No. # 1

Location: E/2 W/2 NW Sec. 24 Twp. 21 Rge. 12 (E)(W) W

County Stafford Total Depth 3637' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Foster was instructed to plug the well as follows:

260' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill  
hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent