

15.185.01904.0001

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SW SW SW

SEC 28 TWP. 21 RGE. 12

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. # 1 Lease Unstead Umstead

Operator Pan American Pet. Co. Address Box 7', Ellinwood, Kansas

Field _____ County c/o G.A. Reynolds
Stafford

Total Depth 3604 Feet.

Plugging Contractor R. & S. Pipe Pulling Co.

Plugging Contractor's License No. # 1

Address Ellinwood, Kansas

(Describe Briefly the manner in which the well was plugged)

Sand back to 3347' and run 6 sax cement with dump bailer. Shot
pipe off--pulled same. Mud to 250' , set rock bridge and 40 sax
cement. Mud to 20'. Set rock bridge and 15 sax cement which cemented
to the base of the cellar.

Donald Truman
District Conservation Agent

Date October 20, 1957

10-22-57

RECEIVED
DISTRICT CONSERVATION

PLUGGING
FILE SEC 28 T 21 R 12w
BOOK PAGE 49 LINE 1

FORM O-12 2-57
M. W. ...

PAN AMERICAN PETROLEUM CORPORATION
CENTRAL DIVISION
FIELD PURCHASE ORDER

15.185.01904.0001

CE NO. 21639

ORDERED FROM State Conservation Commission - Conservation DATE Oct 7, 1957

ADDRESS 211 North Broadway, Wichita, Kansas.

TERMS FOB

DELIVER TO _____

RENDER INVOICE IN DUPLICATE FOR EACH ORDER. SHOW ORDER NUMBER ON ALL COPIES OF INVOICE AND MAIL TO PAN AMERICAN PETROLEUM CORPORATION
Collinswood, Kansas
CITY STATE

QUANTITY	DESCRIPTION	FEA	SYM	UNIT PRICE	AMOUNT
	<i>State fees, Plugging Instructions</i>				

PLUGGING
FILE SEC. 28 T. 21 R. 12W
BOOK PAGE 49 LINE 1

STATE CONSERVATION COMMISSION
OCT 9 1957
CONSERVATION DIVISION
Wichita, Kansas

CHARGE TO M. Winsted # 1 Abid

ORIG. OR CHNG. CONST. OPERATIONS OR REPAIRS
 REPLACEMENT

USED FOR State Fees
BY ACCEPTANCE OF THIS ORDER SELLER OR CONTRACTOR AGREES TO AND SHALL BE BOUND BY THE TERMS AND CONDITIONS PRINTED ON THE BACK HEREOF.

PAN AMERICAN PETROLEUM CORPORATION

BY E. Schneider