

15.185.21127.0000

KANSAS

FORM CP-3  
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-185 21, 127

245 North Water  
Wichita, KS 67202

Operator's Full Name Energy Reserves Group, Inc.

Complete Address 1022 Hoover St., Great Bend, Kansas 67530

Lease Name Leona Walker Well No. 1

Location SE NW SW Sec. 32 Twp. 21S Rge. 12 (~~East~~) (West)

County Stafford Total Depth 3800'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 12:30 Day 25 Month 11 Year 1980  
PM

The above well was plugged as follows:

Sanded back to 3675' and 5 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 4 sx hulls,

15 sx mud-gel, plug, and 125 sx cement.

Max. pres. 500#. Shut in pres. 150#.

Recovered aprox 1750' of 5 1/2" casing.

Plugged back to 3733'.

Top perforation at 3724'.

3796' of 5 1/2" casing cemented with 250 sx cement.

683' of 8 5/8" surface casing cement circ.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 26 1980

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Deane Rankin  
Conservation Division Agent

DATE 12-8-80

INV. NO. 3697-10