

140
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

6-15-1964
RECEIVED
STATE CORPORATION COMMISSION

JUN 15 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Isern-Wells

Complete Address: P. O. Box 486, Ellinwood, Kansas

Lease Name Umstead Well No. # 1

Location CNL NW NE Sec. 32 Twp. 21 Rge. 12 (E) (W)W

County Stafford Total Depth 3599

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 4:00PM Day 12th Month June Year 1964

The Above well was plugged as follows:

282' of 8 5/8" surface pipe, cemented with 125 sacks. 3599' of 5 1/2" long
string, cemented with 125 sacks. Plug back to 3589'. Top perferation
3344'. All perferations had been squeezed. Fluid level was up in the hole.
Plug was pushed to 270', with 10' of rock bridge. 4 sacks of cement with
5% Calcium Chloride was mixed in barrel, and put on plug at 260', through
dump bailer, and let set for 4 hours. Now fluid in hole bailed down, and
21 sacks of cement was added to the plug. Hole was filled with mud to 40',
with 10' of rock bridge, and cemented with 10 sacks to base of the cellar.
1750' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Audie Elving*
Well Plugging Supervisor

DATE 6/15/64
INV. NO. 9304-u