

15.185.12673.0000

Form CP-3  
Rev. 6-26-62

Y  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 10 1964

CONSERVATION DIVISION  
Wichita, Kansas

6-10-1964

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Isern-Wells

Complete Address: P. O. Box 486, Ellinwood, Kansas

Lease Name Umstead Well No. # 2

Location NW NE NE Sec. 32 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3611

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Pipe Pullers Inc.

Address: P. O. Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 4:00PM Day 9th Month June Year 1964

The Above well was plugged as follows:

275' of 8 5/8" surface pipe, cemented with 225 sacks. 3610' of 5 1/2" long  
string, cemented with 100 sacks. Bottom of the hole was sanded to 3550',  
and cemented with 5 sacks. Fluid level was up in the hole. Plug was push-  
ed to 260', with 10' of rock bridge. 2 sacks of cement and 5% calcium  
chloride was mixed in barrel, and put on plug, through dump bailer, and  
let set for 4 hours. Hole bailed down, and 23 sacks of cement was added  
to plug at 250'. Hole was filled with mud to 40', with 10' of rock bridge,  
and cemented with 10 sacks to base of cellar. 1000' of 5 1/2" long string  
was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 6/10/64

INV. NO. 9285-W