



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 52-18

LOCATION CN-NW-SW

SEC. 32 TWP. 21 RGE. 12

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3-B Lease J. W. Walker

Operator Standard Oil & Gas Co Address Box #7 - Ellinwood - Kans.

Field _____ County Stafford

Total Depth 3625 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 1 3/4" - 226ft - Circulated with Cement.
5/8 casing set at 3620ft - Dumped 5 sacks of cement
on bottom of hole - Shot off & P. pulled 3000ft of 5/8 casing -
Filled with mud to 226ft - Bridged 4 sacks of
cement at 226ft - Mud to 20ft - Plug & 10 sacks
of cement to top surface

C. D. Stoughton
District Conservation Agent

Date 9-4-48

PLUGGING
FILE SEC. 3721-R/W
BOOK PAGE 52 LINE 18

9-6-48