

State of Kansas



15.195.30093.00.00

FORM - CP-2
Rev. 9-8-64

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1965

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. J. J. Wenrich of D & D Drlg. Co. Inc., has this
date requested permission to plug the following described well:

Mr. Wenrich guarantees payment of the plugging fee.

Operator's full Name: D & D Drilling Company, Incorporated,

Complete Address: 307 Schweiter Building, Wichita, Kansas.

Lease Name: Price Well No. 1

Location: CSE-NW Sec. 15 Twp. 15 Rge. (E) (W) 21

County Trego Total Depth 4160 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wenrich was instructed to plug the well as follows:

231' -- 8 5/8" surface pipe, cement circulated with 200 Sx.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

"	"	220' with $\frac{1}{2}$ sk. hulls &
		20 Sx. cement.
"	"	40' with $\frac{1}{2}$ sk. hulls &
		10 Sx. cement.

Very truly yours,

M. L. Dechels
Conservation Division Agent