

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 3 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated, has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 West Wichita Avenue, Russell, Kansas.

Lease Name: Brenner Well No. B-3

Location: CNE-NE Sec. 13 Twp. 15 Rge. (E)(W) 21

County: Trego Total Depth 3906' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

167'--8 5/8" Surface casing, cement circulated with 115 Sx.
Top of Dakota section @ 400'.

Circulate hole with heavy mud. Pull DP to 625' and displace 100 Sx. cement thru DP. Pull DP to 185' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent