

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1972
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co., Inc., has this
date requested permission to plug the following described well:Mr. Rowe guarantees payment of the plugging fee.Operator's full Name: Donald C. Slawson,Complete Address: 408 One-Twenty Building, Wichita, Kansas.Lease Name: Messier Well No. A-3Location: 150' East of CNW-SW Sec. 14 Twp. 14 Rge. (E)(W) 22County: Trego Total Depth 4219' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Rowe was instructed to plug the well as follows:349'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 525'.Circulate hole with heavy mud. Pull DP to 750' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent