



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 28 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co. Inc has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Incorporated,

Complete Address: 410 4th National Bank Building, Wichita, Kansas.

Lease Name: Kroeger Well No. 1

Location: NW-NE-SE Sec. 16 Twp. 14 Rge. (E)(W) 21

County: Trego Total Depth 4010 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

243'--8 5/8" Surface casing, cement circulated with 185 Sx.

4008'--5 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to 3997'. No indication of perforations.

Sand well back to 3900' and set 5 Sx. cement with dump bailer. Pull 5 1/2" and squeeze well with 35 sacks gel using 5 sacks hulls in initial gel and follow with 130 Sx. cement.

Very truly yours,

M. L. Nichols
 Conservation Division Agent