

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 9 - 1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Robinowitz Oil CompanyComplete Address: 1322 East 50th St., Tulsa, OklahomaLease Name Tammen Well No. # 1Location App. SW NE NE Sec. 6 Twp. 21 Rge. 12 (E) (W) WCounty Stafford Total Depth 3493'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: B & B Drilling, Inc.Address: 548 Petroleum Bldg., Wichita, Kansas License No. Operation Completed: Hour 2:00PM Day 6th Month May Year 1966

The Above well was plugged as follows:

289' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fluid
level in the hole was at 90'. 1st cementing plug and 1/4 sack of hulls
was pushed in fluid to 260', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged and
cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Aulie Elving

Well Plugging Supervisor

DATE 5/9/66INV. NO. 3178-W