

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 62-21

LOCATION CN/2-NE-SW

SEC. 33 TWP. 16 RGE. 12 W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Schneuers

Operator Bennett & Roberts Oily Co. Address Drawer 232 Russell Ks.

Field _____ County Barton

Total Depth 3370 Feet.

Plugging Contractor Miller Casing Pulling Co.

Plugging Contractor's License No. 12

Address Great Bend Kans

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 3/4" @ 263' c.w.c. 5 1/2" Oil string
set 3369' w/ 75 st Cem. Cement only drilled out
to 3363' top perf. 3343'. Sanded hole to 3330'
and dumped 5 st Cem. shot off and pulled
5 1/2" casing. Mudded hole to 225' set rock
bridge and run 20 st Cem. mud to 35'
rock bridge and 10 st Cem to base of
cellar

9-15-1954

Warren H. Warner
District Conservation Agent

Date Sept 17, 1954

PLUGGING
FILE SEC 33 T 16 R 12 W
BOOK PAGE 12 LINE 21

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS