

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 135-37

LOCATION NW-NW-NE

SEC. 33 TWP. 16 RGE. 12W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Schmoris

Operator Heyes Drilling Co Address Ellinwood - Kans.

Field _____ County Barton

Total Depth 3368 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 1/2" - 178 ft. Circulated with cement
5/8" casing set at 3350 ft. Plugged back from
bottom to 3345 ft with chert - Mixed 5 sacks of
Cement at 3345 ft. Shot off & pulled the 4 1/2" casing -
Mud to 178 ft. Set Rock Bridge & 15 sacks of
Cement 178 ft. Mud to 30 ft. Bridge & 10 sacks
of cement at the surface -
West Supply - Plugging - Contractors*

FEB 13 1950
PLUGGING
FILE SEC 33 TWP 16 RGE 12W
BOOK PAGE 135 LINE 37AS

2-13-1950
E. H. Stough -
District Conservation Agent
Date 2-8-50