


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Stafford County. Sec. 6 Twp. 21 Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner Westgate-Greenland Oil Company
Lease Name Rothgarn "B" Well No. 1
Office Address 1022 Union National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed January 16, 1950 19
Application for plugging filed April 5, 1950 19
Application for plugging approved April 6, 1950 19
Plugging commenced April 18, 1950 19
Plugging completed April 23, 1950 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
surface		1	302	9 5/8"	302	none
			3464	5 1/2"	3464	2880

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Filled with rock to 3460 feet and ran 5 sacks cement, to 3425 feet
Filled with heavy mud from 3425 to 300 feet and ran 20 sacks cement to 260 feet
Filled with heavy mud from 260 feet to 30 feet and ran 10 sacks cement to cellar.

RECORDED
4-29-1950
APR 29 1950

STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Westgate-Greenland Oil Company, Kansas
Address 1022 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. E. Bitler (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. E. Bitler
1022 Union National Bank Building, Wichita 2, Ks
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of April, 19 50
Esther L. Russell
Notary Public.

My commission expires May 25, 1953

22-5138-s 9-48-10M
PLUGGING
FILE SEC-6731-R174
BOOK PAGE 146 LINE 25

COMPANY: Westgate Greenland Oil Co.
 CONTRACTOR: Jackson Drilling Corp.
 FARM: Rothgarn B-1
 LOCATION: SE/SE/NE Section 6-21-12W
 Stafford County, Kansas
 COMMENCED: January 1, 1950
 COMPLETED: January 10, 1950 Rotary
 January 16, 1950 Cardwell

0	to	220	Sand & Shale
220	to	365	Red Bed
365	to	715	Red Bed & Shale
715	to	755	Anhydrite
755	to	1180	Shale & Shells
1180	to	1320	Shale & Salt
1320	to	3120	Shale & Lime
3120	to	3205	Shale
3205	to	3210	Lime
3210	to	3270	Lime & Shale
3270	to	3415	Lime
3415	to	3468	Lime & Shale
3468	to	3471	Arbuckle
		3471 T.D.	Rotary
		3529 T.D.	Cardwell

9 5/8" casing set at 302 feet. Cemented with 225 sacks cement and 2 sacks calcium chloride.

5 1/2" casing set at 3464 feet. Cemented with 60 sacks cement.

Tops: Lansing 3220
 Arbuckle 3460

Dry

Measurements from top of derrick floor.

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Rothgarn B-1, Section 6-21-12W, Stafford County, Kansas, as reflected by files of the Jackson Drilling Corporation.


 Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas this 23rd day of January, 1950.

FILED
 REC'D SEC. 6-21-12W
 PAGE 146 LINE 25


 Dorothy J. Wilson

My commission expires November 30, 1950.