

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

15.083.20965-0000  
 Form CP-4  
 Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Hodgeman SEC. 15 TWP. 21 RGE. 24 E/W  
 Location as in quarters or footage from lines:  
SE NE NE


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Overland Energy, Inc.  
 Lease Name Goebel Well No. 1-15  
 Office Address 1640 Grant St., Suite 301, Denver, CO 80203  
 Character of Well (Completed as Oil, Gas or Dry Hole): dry hole  
 Date Well Completed 4/16/82  
 Application for plugging filed 4/23/82  
 Plugging commenced 5/3/82  
 Plugging completed 5/4/82  
 Reason for abandonment of well or producing formation  
Less than 1% oil on initial completion  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Dorrant  
 Producing formation Mississippian Depth to top 4426' bottom 4445' T.D. 4470'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Mississippian</u>	<u>water</u>	<u>4412'</u>	<u>4469'</u>	<u>4 1/2"</u>	<u>3/20/82</u>	<u>5/4/82</u>
				<u>8 5/8"</u>	<u>3/6/82</u>	<u>--</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet for each plug set.

- (1) Placed 5 cu ft sand plus 6 sx common cmt w/dump bailer from PBTD 4454' to 4322'
- (2) Cut 4 1/2" casing off at 2947' and recovered same
- (3) Pumped 70 sx common cmt w/3 sx Hulls and 4% gel followed by 70 sx 50-50 pozmix w/4% gel and 3% CaCl. Set plug immediately below surface pipe from 875' to 372'. Maximum pump pressure 1800 psi, SIP 500 psi.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hembree Well Service, Inc.

STATE OF Colorado COUNTY OF Denver, ss.  
Richard W. Webb (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) *R. W. Webb*  
1640 Grant St., Suite 301, Denver  
 (Address) CO 80203

SUBSCRIBED AND SWORN TO before me this 5th day of May, 19 82

*Barbara Williams*  
 RECEIVED  
 STATE CORPORATION COMMISSION Public.

My Commission expires: August 17, 1984

MAY - 7 1982

CONSERVATION DIVISION  
 Wichita, Kansas