

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027

Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

HODGEMAN

County, Sec. 5 Twp. 12 S Rge. (E) 24 (W)

Location as "NE/CNWxSWx" or footage from lines C W/2 SW NE

Lease Owner DANE G HANSEN TRUST

Lease Name HUMBURG RANCH Well No. 1

Office Address LOGAN, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed JUNE 2 1972

Application for plugging filed JUNE 2 1972

Application for plugging approved JUNE 2 1972

Plugging commenced JUNE 2 1972

Plugging completed JUNE 2 1972

Reason for abandonment of well or producing formation TOO LOW STRUCTURALLY

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well EDGAR J. EVES, SUBLETTE, KANSAS

Producing formation Depth to top Bottom Total Depth of Well 4443 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	366.11'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED WITH HEAVY MUD TO 850'. SET PLUG.  
PUT IN 80 SACKS CEMENT. FILLED WITH HEAVY  
MUD TO 360'. SET PLUG. PUT IN 30 SACKS  
CEMENT. FILLED WITH HEAVY MUD TO 40'.  
SET PLUG. FILLED TO TOP WITH 10 SACKS  
CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 14 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor C-G DRILLING CO.  
Address 1107 UNION NATIONAL BUILDING, WICHITA, KANSAS 67202

STATE OF KANSAS COUNTY OF SEDGWICK, SS.  
G. F. GALLOWAY (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway  
1107 Union National Bldg.  
(Address)

Subscribed and sworn to before me this 7th day of June, 1972

My commission expires December 7, 1972

Phyllis Buchanan  
Notary Public.



W E L L L O G

OPERATOR: DANE G. HANSEN TRUST  
 WELL NAME: HUMBURG RANCH #1 LOCATION: C W/2 SW NE SEC 5-T21S-R24W  
 COUNTY: HODGEMAN STATE: KANSAS  
 WELL COMMENCED: MAY 22, 1972 WELL COMPLETED: JUNE 1, 1972  
 ELEVATION: 2306 KB TOTAL DEPTH: 4443'  
 PRODUCTION: DRY & ABANDONED RIG NO: 1  
 CASING - 8-5/8": 11 JTS, 366.11' W/225 SX POZMIX (60-40) 3% CAL CH 2% GEL  
 5-1/2": .....

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	835	SHALE		
835	1530	SHALE & SAND		
1530	1575	ANHYDRITE		
1575	1815	SHALE & RED BED		
1815	2060	SHALE		
2060	2700	SHALE & LIME		
2700	2840	LIME		
2840	3100	LIME & SHALE		
3100	3215	SHALE		
3215	3415	SHALE & LIME		
3415	3595	SHALE		
3595	3795	SHALE & LIME		
3795	4406	LIME		DST #1 4294'-4315'
4406	4433	MISSISSIPPIAN		DST #2 4409'-4433'
4433		RTD		DST #3 4426'-4443'

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 14 1972  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 COUNTY OF SEDGWICK ) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. H. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, This 5th day of June, 1972.

MY COMM. EXP. DEC. 7, 1975

Phyllis Buchanan  
 PHYLLIS BUCHANAN - NOTARY PUBLIC

