


15-009-00381-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Barton County. Sec. 33 Twp. 16S Rge. (E) 12 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW SE  
Lease Owner Brooks Pierce et al  
Lease Name Prosser Well No. 1  
Office Address 1208 Union National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 12, 1951  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced March 17, 1951  
Plugging completed March 17, 1951  
Reason for abandonment of well or producing formation.....  
If a producing well is abandoned, date of last production.....19.....  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?.....

Name of Conservation Agent who supervised plugging of this well.....  
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3353 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Pipe				8-5/8"	210'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

- 3353' - 3340' Crushed Rock
- 3340' - 3305' 5 Sacks Cement
- 3305' - 205' Heavy Mud
- 205' - 195' Permanent Rock Bridge
- 195' - 150' 15 Sacks Cement
- 150' - 35' Heavy Mud
- 35' - 30' Rock Bridge
- 30' to Bottom of Cellar - 10 Sacks Cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....  
Address.....

STATE OF Kansas, COUNTY OF Sedgwick, SS.  
..... (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Brooks Pierce

1208 Union Nat'l Bank Bldg, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of March

My commission expires September 8, 1954

**RECEIVED**  
STATE CORPORATION COMMISSION  
[Signature]  
Notary Public.

MAR 21 1951

CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC 33T 16 R 12W  
BOOK PAGE 661W 40

BROOKS PIERCE DRILLING COMPANY  
 UNION NATIONAL BANK BUILDING  
 WICHITA 2, KANSAS

PROSSER NO. 1  
 NW NW SE of Section 33-16S-12W  
 Barton County, Kansas

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Shale & Rock	0	130	8-5/8" Surface Pipe @ 205', cemented with 150 sacks cement and 100 lbs. of calcium chloride.
Shale & Shells	130	215	
Sand	215	270	
Shale & Shells	270	470	
Red Bed	470	760	
Anhydrite	760	795	
Shale & Shells	795	1220	
Salt & Shale	1220	1400	
Shale & Shells	1400	1490	
Lime	1490	2095	
Shale & Lime	2095	2110	Set casing.
Lime	2110	2160	
Lime & Shale	2160	2235	
Shale	2235	2570	
Shale & Shells	2570	2695	
Shale & Lime	2695	2820	
Lime	2820	2930	
Lime & Shale	2930	3040	
Shale	3040	3070	
Lime	3070	3344	
Arbuckle	3344	3353	

Total Depth: 3353'

I hereby certify the foregoing to be a true and accurate Driller's Log of the formations encountered in the above well.

BROOKS PIERCE DRILLING COMPANY

By Brooks Pierce  
 Brooks Pierce, Owner

Subscribed and sworn to before me this 12th day of February, 1951.

Louise Bowman  
 Notary Public  
 My Commission expires September 8, 1954.  
 RECEIVED  
 MAR 21 1951  
 CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE SEC 52-16-PLU  
 PAGE 66-16