


15-009-06298-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 33 Twp. 16 Rge. 12W (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines CN/2 NE SW
Lease Owner Bennett & Roberts Drilling Co.
Lease Name Schneweis Well No. 1
Office Address Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 8/27 19 54
Application for plugging filed 8/30 19 54
Application for plugging approved 9/8 19 54
Plugging commenced 9/8 19 54
Plugging completed 9/14 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Red Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3370 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	263'	None
				5 1/2"	3369'	1781'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with crushed rock to 3330', dumped 5 sacks cement with dump bialer. Top of cement, 3295'. Filled with mud to 225', Set rock bridge, dumped 20 sacks cement. Top of cement, 165'. Filled with mud to 35', set rock bridge, dumped 10 sacks cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Co.
Address Great Bend, Ks.


STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of Septm., 19 54

My commission expires 6/17/58

Clara Hummel
Notary Public.



RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1954
CONSERVATION DIVISION
Wichita, Kansas
9-21-1954

Bennett & Roberts Drilling Co.
Schnewsis #1

CN/2 NE SW Sec. 33-16-12
Barton County, Kansas

R. T. D. 3370'

Comm: 8/12/54
Comp: 8/22/54

Set 3 5/8" Csg. @ 263' w/175 sx cmt.
Set 5 1/2" Csg. @ 3369' w/75 sx cmt.

Formations	Depth
Surf. Soil, shale & post rock	35'
Shale, Stks Sand	170
Sand	215
Shale & Shells	340
Sand	390
Hard Sand & Shale	450
Shale	510
Red Bed & Shale	755
Anhydrite	785
Shale	795
Shale & Lime Streaks	1100
Shale & Broken Lime	1200
Salt, Shale & Shells	1320
Shale & Lime Shells	1430
Shale	1460
Lime & Shale	1635
Shale	1680
Lime	1750
Lime & Shale	1830
Lime	1920
Lime & Shale	1925
Lime	2070
Lime & Shale	2420
Shale & Shells	2450
Shale	2500
Lime & Shale	2935
Lime	2980
Heebner	2984
Lime	2998
Lime & Shale	3070
Lime	3370

RECORDED
STATE CORPORATION COMMISSION
SEP 2 1954
CONSERVATION DIVISION
Topeka, Kansas

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is correct to
the best of my knowledge. BENNETT & ROBERTS DRILLING CO.

Dr. J. L. Baker

Subscribed and sworn to before me this 24th day of August, 1954.

W. L. Lamm
Notary Public

My commission expires 6/17/58

