

STATE OF KANSAS
STATE CORPORATION COMMISSION
10 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-071580000

LEASE NAME Scheweis

WELL NUMBER #2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 33 TWP. 16S RGE. 12W (E) or (W)

COUNTY Barton

Date Well Completed 1949

Plugging Commenced 5-19-98

Plugging Completed 5-20-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS P.O. Box 783188 Wichita, Ks. 67278-3188

PHONE (316) 691-9500 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

When plugging proposal was approved on (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filled? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3330'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	190	None
				5-1/2"	3329'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from feet to feet each section.
Shot 5-1/2" casing @1500', 785' & 385'. Pumped 25 sacks cement w/100" hulls down backside Ran 2-1/2" tubing to 3200', pumped 50 sks. cement w/200# hulls, pumped 75 sks. cement w/300# hulls @2450', pumped 110 sks. cement w/100# hulls @1500' and circulated. Pulled out tubing and pumped 50 sks. cement down 5-1/2" casing. 60/40 pos. 10% gel Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 26th day of May, 19 98

Irene Herzberg
Notary Public

My Commission Expires:

