

OF KANSAS  
CORPORATION COMMISSION  
Colorado Derby Building  
Atta, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR American Warrior, Inc.

ADDRESS PO Box 399 Garden City, KS. 67846

PHONE#(316) 275-2963 OPERATORS LICENSE NO. 4058

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-2-1996 (date)

by Marion Schmidt- District 4 (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? NONE ON FILE

Producing Formation Arbuckle Depth to Top 3338 Bottom 3341 T.D. 3341

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	300	0	8-5/8	8-5/8	NONE
	Production	3338	0	4-1/2	3338	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Ran 2-3/8" tubing to 1510', mix 200 sacks of 65/35 poz 6% gel, pumped down tubing mix 300 sacks of 60/40 poz 8% ges with 1000 #s of bulls, pumped down tubing 2-3/8" tubing, pumped 75 sacks of cement down casing, hookup to annulus, pumped 35 sacks pressure to 300#

(If additional description is necessary, use BACK of this form.) 1-2-1996


Name of Plugging Contractor American Warrior, Inc. License No. 4058

Address PO Box 399 Garden City, KS. 67846

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior, Inc.


STATE OF Kansas COUNTY OF Finney ss.


Kevin Wiles Sr (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) 

Kevin Wiles Sr.

(Address) PO Box 399 - Garden City, KS. 67846



  
Debra J. Purcell  
Notary Public