

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

BELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-009-22,505-00-00

LEASE NAME SCHNEWEIS

WELL NUMBER 2

4290 Ft. from S Section Line

3860 Ft. from E Section Line

SEC. 33 TWP. 16S RGE. 12 (E) or (W) X

COUNTY BARTON

Date Well Completed _____

Plugging Commenced 12-20-96

Plugging Completed 12-20-96

LEASE OPERATOR SMOKEY VALLEY RESOURCES

ADDRESS 1325 HWY 56, LYONS, KS 67554

PHONE(S) (316) 257-5529 OPERATORS LICENSE NO. 4424

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-20-96 (date)

by HERB DEINES (XCC District Agent's Name).

Is ACO-1 filed? YES if not, is well log attached? _____

Producing Formation ARB. Depth to Top 1885' Bottom 3344' T.O. 3344'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>ARB</u>	<u>Oil & WATER</u>	<u>3300'</u>	<u>3344'</u>	<u>5 1/2"</u>	<u>3344'</u>	<u>2006'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set 1 1/2" to 3344' w/sxs. O.H. 3344' - 3347'. Sanded to 3290' and spotted 5 sxs cement with dump bailer. Shot casing at 2006' and pulled to 1450'. Mixed and pumped 100 sxs cement with 300# hulls. Pulled casing to 800' and pumped 35 sxs with 150# hulls. Pulled casing to 400' and pumped 30 sxs cement with 150# hulls. Pulled casing to 150' and circulated cement with 20 sxs. Pulled casing with cement in cellar.

Name of Plugging Contractor QUALITY WELL SERVICE, INC. License No. 31925

Address 249 E. BETH DR., STERLING, KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GEORGE SALING

STATE OF KANSAS COUNTY OF RICE, ss.

(Employee of Operator) or (Operator) o above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) George Saling

(Address) 1325 Hwy 56, Lyons, KS 67554

SUBSCRIBED AND SWORN TO before me this 23rd. day of April, 1997

My Commission Expires: August 24, 1997



Form 9-1
 Revised 05-88

RECEIVED
 KANSAS CORP COM
 1997 MAR - A 11